

कुमाऊँ विश्वविद्यालय, नैनीताल

पत्रांक:केयू/वि०नियो०/ 66

दिनांक:- 18/06/2025

निविदा सूचना

कुमाऊँ विश्वविद्यालय, नैनीताल में लघु निर्माण/अनुरक्षण सम्बन्धी कार्यो हेतु विश्वविद्यालय में पंजीकृत ठेकेदारों से दिनांक 02.07.2025 समय मध्यान्ह 12:00 बजे तक निविदाएं डाक/दस्ती/निविदा बॉक्स/कोरियर से आमंत्रित की जाती हैं। विस्तृत जानकारी एवं निविदा फार्म विश्वविद्यालय की वेबसाइट www.kunainital.ac.in से अपलोड की जा सकती है।


कुलसचिव

प्रतिलिपि:-निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

1. वित्त नियन्त्रक, कु०वि०वि०, नैनीताल।
2. स्थानीय संवाददाता हिन्दुस्तान नैनीताल को इस आशय से प्रेषित की उक्त निविदा सूचना को अपने समाचार पत्र के कुमाऊँ संस्करण में 6सेमी०X3सेमी० में 10 प्रतिशत छूट प्रदान करते हुए प्रकाशित कर बिल दो प्रतियों में विश्वविद्यालय को प्रेषित करें।
3. सूचना पट्ट प्रशासनिक भवन/डी०एस०बी० परिसर, नैनीताल।


कुलसचिव

कुमाऊँ विश्वविद्यालय, नैनीताल


पत्रांक:केयू/वि०नियो०/6649

दिनांक:- 18-6-2025

निविदा सूचना

अधोलिखित लघु निर्माण/अनुरक्षण कार्य के लिए विश्वविद्यालय में पंजीकृत ठेकेदारों से दिनांक 02.07.2025 समय मध्याह्न 12:00 बजे तक निविदाएं डाक/दस्ती/कोरियर/निविदा बॉक्स के माध्यम से आमंत्रित की जाती हैं, जो उसी दिन अपराह्न 1:00 बजे विश्वविद्यालय कार्यालय में खोले जायेंगे। निविदादाता अथवा उनके प्रतिनिधि निविदा खोलते समय उपस्थित रह सकते हैं। निविदा खोलने की तिथि में अवकाश होने पर निविदा अगले कार्य दिवस में खोले जायेंगे। विस्तृत जानकारी एवं निविदा फार्म विश्वविद्यालय की वेबसाइट www.kunainital.ac.in से अपलोड की जा सकती है।

क्र०सं०	कार्य का नाम	अनुमानित लागत	धरोहर राशि	निविदा फार्म मूल्य	कार्य पूर्ण करने की अवधि
1.	डी०एस०बी० परिसर में शूटिंग रेंज शेड का निर्माण कार्य।	रु० 14.95 लाख	रु० 30,000.00	रु०1,770.00	30 दिन
2.	डी०एस०बी० परिसर भौतिक विज्ञान विभाग भवन से रसायन विज्ञान विभाग भवन एवं संगीत विभाग से जन्तु विज्ञान विभाग चिकर्ड टाइल्स लगाने का कार्य।	रु० 5,24,502.00	रु० 10,500.00	रु०1,180.00	21 दिन


कुलसचिव

प्रतिलिपि:-निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

1. कम्प्यूटर प्रोग्रामर, कु०वि०वि० को उक्त सूचना विश्वविद्यालय वेबसाइट में अपलोड करने हेतु।
2. सूचना पट्ट, प्रशासनिक भवन, कुमाऊँ विश्वविद्यालय, नैनीताल।


कुलसचिव

कुमाऊँ विश्वविद्यालय, नैनीताल

निविदा पत्र

1. निविदा प्रपत्र सीलबन्द लिफाफे में अधोहस्ताक्षरी के कार्यालय में निर्धारित तिथि एवं समय तक दस्ती/डाक/कोरियर/निविदा बाक्स में डाली जानी आवश्यक होगी।
2. प्रत्येक निविदा के साथ रू0 100.00 का नॉन ज्यूडिशियल स्टाम्प पर एक रुपये का हस्ताक्षरयुक्त रसीद टिकट संलग्न होना चाहिए।
3. प्रत्येक निविदा के साथ निर्धारित शुल्क विश्वविद्यालय कैश काउन्टर की रसीद के रूप में संलग्न हो एवं निविदा के साथ धरोहर राशि एफ0डी0आर0/एन0एस0सी0 के रूप में वित्त नियन्त्रक, कुमाँऊ विश्वविद्यालय के पक्ष में बन्धक होनी चाहिए।
4. निविदाता को चाहिए कि वे निविदा लेने से पूर्व कार्यस्थल का निरीक्षण कर लें।
5. समस्त कार्य लोक निर्माण विभाग (डी0एस0आर0) द्वारा समय-समय पर निर्गत निर्धारित मानकों/शर्तों के अनुरूप सम्पादित किये जायेंगे।
6. किसी एक अथवा समस्त निविदाओं को स्वीकृत/अस्वीकृत करने का अधिकार अधोहस्ताक्षरी के पास सुरक्षित होगा।



कुलसचिव
कुमाँऊ विश्वविद्यालय, नैनीताल

3

Kumaun University Nainital

Tender form

Name of work- Construction of Tin shed shutting rang at D.S.B. Campus Nainital.

Date of Calling tender- 19.06.2025

Cost of tender form- Rs. 1,170.00

Time of completion- 30 Days

Date of opening tender- 02.07.2025


Earnest money - Rs. 30,000.00

Validity of tender- 45 Days

S.N.	Item of work	Quantity	Unit	Estimated Rate in Rs
1.	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. 10.16.1 Hot finished welded type tubes	4128.49	Kg	194.40
2.	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm, joints mitred and welded by angle iron 35x35x5 mm or 35x 5 mm flat pieces to the existing T-iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per the direction of Engineer-In-charge.	400.	Kg	130.50
3.	Fixing of old G.I. sheet & repairing with putti & epoxy complete all	320.38	Sqm	300.00
4.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in 6.4.2 Cement mortar 1:6 (1 cement : 6 coarse sand)	20.08	Cum	9105.95
5.	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	2.92	Cum	6812.00
6.	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with : 10.30.1 4.0 mm thick glass panes	4.80	Cum	1064.65
7.	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	5.29	Cum	11505.50
8.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	415.26	Kg	107.10
9.	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with :	11.71	Cum	7311.25
10.	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	640.76	Sqm	180.85
11.	12 mm cement plaster of mix 1:6 (1 cement : 6 fine sand)	88.35	Sqm	333.35

Note- All the work shall be carried out as per P.W.D.(D.S.R.) specification and directed by Engineer In charge I/We tender.....% below/above on the given Estimated rates.

Sig. of contractor
(with full address)


Registrar



5

Kumaun University Nainital

Tender form

Name of work- Chequerred tiles foot path work physics deptt to chemistry deptt. and music deptt. To zoology deptt at D.S.B. Campus Nainital.

Date of calling tender- ~~10~~ 06.06.2025

Cost of tender form- Rs. 1180.00

Time of completion- 21 Days

Date of opening tender- 02.07.2025

Earnest money - Rs. 10,500.00

Validity of tender- 45 Days

S.N.	Item of work	Quantity	Unit	Estimated Rate in Rs
1.	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	15.16	Cum	7878.50
2.	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Medium shade pigment using 50% white cement 50% Grey cement	295.20	Sqm	1328.35
3.	12 mm cement plaster of mix : 13.1.2 1:6 (1 cement: 6 fine sand)	39.12	Sqm	333.35

Note- All the work shall be carried out as per P.W.D.(D.S.R.) specification and directed by Engineer In charge I/We tender.....% below/above on the given Estimated rates.

Sig. of contractor
(with full address)


Registrar

